GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated 20th August 1927.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer in Mysore, Bangalore, up to 2 P.M. on 20th September 1927, for constructing the Oil and Pump House near the New Transformer Station, Narasimharaja Mohalla, Mysore. The tenders will be opened in public at 2 P.M. on Tuesday the 20th September 1927. The time required to complete the work and montly progress, should be indicated, as these will be some of the Chief Factors in the award of tenders.

2. The plans, detailed estimate and the conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, and the Superintendent's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the Oil and Pump House at Mysore," in default of which, tenders will be rejected.

5. Final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. The construction work should be started within a fortnight from the date of notification of the acceptance.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Water for construction should be got at the contractor's own expense.

12. Specifications for work are those recognised by the Mysore Public Works Department and Marryot's Specifications.

13. The contractor should be bound by the conditions of the Schedule Contract of the Electrical Department.

Statement showing the approximate quantities of work for constructing the Oil and Pump House at Mysore.

	Items of work	Unit	Quantity
1.	(*a*) Excavation, ordinary soil with 50 ft. lead	C.yd.	279
	(*b*) Do soft rock do	,,	558
2.	(*a*) Concrete stone jelly in surki mortar—Concrete 1, 2 Mortar, 1 Lime, 2 Sand and ½ Surki.	C.ft.	2,028
	(*b*) Coursed rubble stone in surki mortar, foundation and basement. Mortar, 1 lime, 2 sand, ½ surki.	,,	1,200
	(*c*) Burnt brick in surki mortar...Mortar 1 lime, 2 sand and ½ surki.	,,	1,855
	(*d*) Burnt brick in mortar 1 : 2½	,,	2,944
	(*e*) Burnt brick in mortar archwork	,,	100
	(*f*) Stone slabs 6" thick roughly dressed and set in mortar ...	S.ft.	133
	(*g*) Chunam plastering, 2 coats	Sqr.	41·63
	(*h*) White and colour washing, 2 coats	,,	41·63
	(*i*) Cement plastering ½" thick	,,	30·00
	(*j*) Chunam pointing with linning	,,	0·60
	(*k*) Binding wall 1—1/8 feet × ¾ ft. brick in mortar and chunam plastered.	R.ft.	52
	(*l*) Mortar band 6" × 3" over roof	,,	56
	(*m*) Plain brick cornice 6" projection	,,	52
3.	Flooring on 6" stone jelly concrete with cement plastering ½" thick on top.	Sqr.	5·28
4.	(*a*) Roofing with 24 B. W. G. corrugated G. I. sheets to overlap 2 corrugations at sides and 12" at ends, with G. I. screws and lead washers, and mangowood ceiling 1" thick.	,,	12·18
	(*b*) Do without ceiling	,,	18·02

	Items of work	Unit	Quantity
	(*c*) G. I. ridge sheeting plain, 24 B. W. G. 2 feet wide with washers bolts, etc..	R.ft.	90
	(*d*) Teakwood work with woodoiling two coats	C.ft.	45·92
	(*e*) Teakwood door panelled, 1½" shutters with bolts, hinges, etc., frames 4½"×6". *Vide* Drg. No. M. 149.	S.ft.	130
	(*f*) Teakwood glazed windows 1¼" shutters with bolts, hinges, etc., frames 4"×5" with iron bars ¾" dia., 4" C to C. *Vide* Drg. No. M. 149.	,,	155
	(*g*) Silver grey silicate painting three coats..	Sqr.	9·51
5.	(*a*) Rolled steel I beams including fixing charges	Cwt.	3·21
	(*b*) Steel rails S. M. R. Secondhand 40 lbs. including cutting to sizes and fixing.	,,	73
	(*c*) One and a half inches Angle Iron brackets with anchoring bolts, etc., to support the roof.	Each	23
6.	Cement concrete (1 : 2½ : 5) foundation	C.ft.	89
7.	Constructing drains 9" deep all round the Oil and Pump House with surki concrete and cement plastering ½" thick.	R.ft.	130

N.B.—For items 4 (a) and (b) zinc sheets will be supplied by the Department. Price to be quoted for issuin screws and washers and fixing the sheets.

B. KRISHNA RAO,
For *Chief Electrical Engineer*
to the Government of Mysore

KOLAR DIVISION.

FORM OF ADVERTISEMENT.

Dated 22nd August 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 12th September 1927, for restoring Kiruvara Minor Tank, Reg. No. 88, Srinivaspur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 2 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified willibe executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred only in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kiruvara Minor Tank," Srinivaspur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates in the tender should be noted in figures as well as in words.